



**SUPPLY AND FIXING OF GALVANISED WELDED MESH FENCE  
AT  
SODNAC WELLNESS PARK, CANDOS HILL**

**Procurement Reference No.: EWF/2023-2024/OAB/01**

**To: All Prospective Bidders**

Dear Sir/Madam,

**Addendum No.1**

Following request for clarifications received from potential bidders during a pre-bid meeting held on 30 August 2023, please find below the corresponding required information:

<b>S/N</b>	<b>Queries/Proposals Received</b>	<b>Reply from EWF</b>
a.	Replace "Beta Fence" by Galvanised Welded Panel Fence	The words "Beta Fence" has been removed.  The required works are for the <b>"Supply and Fixing of Galvanised Welded Panel Fence"</b> .
b.	Align Section 3 of page 2 of the document with Section GCC57.2 (g)	Section 3 of the bid document refers to the completion time of 120 days whereas Section GCC57.2 (g) refers to situation where "the Contractor has delayed the completion of the Works by the number of days for which the maximum amount of liquidated damages can be paid, as defined in the PCC". Please refer to GCC (Ref: W/GCC10/), for the Procurement of Works (available on website (ppo.govmu.org) as stated at

		Section (IV), Page 17 of the bid document.
c.	Review completion time up to 5 months.	The completion time of 120 days from start date of works has been revised to 150 days from start date of works.
d.	Schedule of Daywork Rates	Bidders to quote for rate per hour only.
e.	Closing date to be extended given amendments proposed	The closing date has been extended to <b>Monday 09 October 2023 at 15.00hrs.</b>
f.	Lower minimum amount of liquidated assets and/or credit facilities from MUR 10M (Page 4 Section 10 d)	Minimum amount of liquidated assets and/or credit facilities has been reviewed from MUR10M to MUR8M.
g.	Define rainfall extent in millimeters	The term “exceptionally adverse weather conditions” is hereby defined as any one of the following events: (1) 100 mm rainfall or above recorded in one day at the nearest rain station; (2) An official declaration of “Torrential Rain” by the Meteorological Department of Mauritius; and (3) Cyclone warning Class III or IV.
h.	Client to arrange for the supply of Power and Water and contractor to refund additional bills incurred	Arrangement for the supply of Power and Water will be made on site and contractor will have to refund the excess charges incurred.
i.	Add foundation details as well as structural details	Please refer to drawings SWP 02 dated 05/09/2023. [Annex A]
j.	Add details on reinforcement of foundation	Please refer to drawings SWP 02 dated 05/09/2023. [Annex A]
k.	Concrete foundation grade to be reviewed to N30	Concrete foundation grade has been maintained to <b>15N/mm<sup>2</sup></b>
l.	Base of galvanized pole to be increased from 300x300 to 500x500	Base of galvanized pole has been reviewed to 450x450  Please refer to drawings SWP 02 dated 05/09/2023. [Annex A]
m.	To add details on type of panel fence e.g., Colour, thickness, diameter etc.	Please refer to revised BOQ at Annex B at item SN11
n.	Panel fence dimensions to define – height from ground level and total height from ground to finishing	Please refer to revised BOQ at Annex B at item SN11 and refer to drawing SWP01 at Annex C.

o.	Clips and accessories to panel fence (Item 10 of BoQ) to include panel details	Please refer to revised BOQ at Annex B at item SN11
p.	To add blocks to slopy ground towards hill sides	Please refer to drawings SWP01 at Annex C and SWP03 at Annex D of this Addendum
q.	Removed chain link fencing to be handed over to whom	Refer to Section III, Paragraph 1, Page 14 of the bid document: "Existing chain link fencing together with wooden poles to be returned to client [EWF/SMF]". Only Concrete debris to be carted away.
r.	Side gates to be kept, removed or replaced	Side gates to be kept as is.
s.	Three (3) main gates - to be keep same or to be replaced with same material	Three (3) main gates to be kept as is.
t.	Preliminary & General (P&G) to be added in BoQ	Same has been termed as <b>Provisional Sum</b> in the BOQ (Page 12) of the initial Bid Document as well as the revised BOQ at Annex B.
u.	Amendments to Scope of Works/ Specifications/ Bill of Quantities	An amended copy of BoQ is at Annex B and Revised Scope of Works is at Annex E.
v.	Additional detailed drawings to work out and submit	Please refer to drawings SWP01 & SWP03 at Annexes C & D of this Addendum.

2. Bidders are hereby informed that the closing date has been revised to **Monday 09 October 2023 by latest 15.00hrs** at latest. (See (e) above).

3. Relevant report on pre-bid meeting held on 30 August 2023 have been uploaded on the Public Procurement Portal.

4. Prospective bidders are kindly requested to take note of this addendum and submit their offers accordingly.

**The Ag. General Manager  
Employees' Welfare Fund  
6<sup>th</sup> Floor  
Moorgate House,  
Sir William Newton Street  
Port Louis, 11328**

**14 September 2023**