REVISED BOQ for replacing chain link fencing with beta fence at SWP

S N	Description of task	Unit	Qty	Rate per Unit (Rs)	Amount (Rs)
01	Requisition. Removal of existing chain link fence, wooden treated pine poles, etc. And handing over same to client.	RM	2000		
02	 Excavation. 1) Excavating in trench to receive strip footing and deposition of in temporary spoil heaps on the site. 	M ³	225		
	 Excavating from ground level in pits to receive column bases and depositing in temporary spoil heaps on site. 	M ³	60		
03	Back filling to excavation. Selected excavated materials arising from spoil heaps deposited and compacting same in layers not exceeding 200 mm in back backfill to excavation to engineer's specifications.	M ³	140		
04	Carting away. Haul up from spoil heaps and remove surplus excavated material from site.	M ³	145		
05	Concrete casting. Plain in-situ concrete as blinding layer 50 mm thick under bases, foundations and the like.	M ³	45		
06	Low block wall	M ²	575		
07	Reinforced in-situ concrete grade 15 N/mm ² as described. 1) As coping cast against fare face of formwork.	M ³	15		
	 As column foundation cast against face of excavation. 	M³	50		
	 As column base cast against fare face of form work. 	M ³	12		
08	Form work. Labour and material for formwork, strutting at edge of bed.	M ²	200		
09	 Labour and material, mild steel reinforcement MS 34 hot rolled plain mild steel 1) To concrete members, 6 mm dia bars as links for surface bed. 	Unit	350		
	 To concrete members, 6 mm dia bars as links for columns. 	Unit	375		
10	Labour and material for high tensile steel reinforcement MS 34 hot rolled high yield steel to concrete members in general. 1) 8 mm dia bars for columns and coping.	Unit	600.		
	2) 8 mm dia bars for column footings.	Unit	320		
11	 Labour and material for fixing and securing beta fence. Welded mesh panel fence, colour green, 2500x1730, 5mm dia, powder coated. 	Unit	800		
	 Powder coated "H" Metallic poles, 2500mm high, powder coated. 	Units	801		
	 Eight powder coated metallic clips and screws per panel (four on each end). 	Units	6400		

ANNEX B

Provisional Sum, if any	
sive of VAT (Carried forward to Bid Submission Form)	
VAT @15%VAT (if applicable)	
Total Amount, inclusive of VAT	